# HITACHI

KAOHSIUNG HITACHI ELECTRONICS CO.,LTD P.O. BOX 26-27 2,13TH EAST ST. K.E.P.Z. KAOHSIUNG TAIWAN R.O.C. TEL:(07) 821-5811 ( 7 LINE) FAX:(07) 821-5815

FOR MESSRS.

DATE. Sep.05,2008

#### CUSTOMER'S ACCEPTANCE SPECIFICATIONS

# SP14Q011-T1A CONTENTS

No.	ITEM	SHEET No.	PAGE
1	COVER	7B64PS 2701- SP14Q011-T1A-2	1-1/1
2	RECORD OF REVISION	7B64PS 2702- SP14Q011-T1A-2	2-1/1
3	GENERAL SPECIFICATION	7B64PS 2703- SP14Q011-T1A-2	3-1/1
4	ABSOLUTE MAXIMUM RATINGS	7B64PS 2704- SP14Q011-T1A-2	4-1/1
5	ELECTRICAL CHARACTERISTICS	7B64PS 2705- SP14Q011-T1A-2	5-1/4~4/4
6	OPTICAL CHARACTERISTICS	7B64PS 2706- SP14Q011-T1A-2	6-1/3~3/3
7	BLOCK DIAGRAM	7B64PS 2707- SP14Q011-T1A-2	7-1/1
8	INTERFACE TIMING	7B64PS 2708- SP14Q011-T1A-2	8-1/3~3/3
9	OUTLINE DIMENSIONS	7B63PS 2709- SP14Q011-T1A-2	9-1/2
		7B64PS 2709- SP14Q011-T1A-2	9-2/2
10	QUALITY STANDARD	7B64PS 2710- SP14Q011-T1A-2	10-1/4~4/4
11	PRECAUTION IN DESIGN	7B64PS 2711- SP14Q011-T1A-2	11-1/3~3/3
12	DESIGNATION OF LOT MARK	7B64PS 2712- SP14Q011-T1A-2	12-1/1
13	PRECAUTION FOR USE	7B64PS 2713- SP14Q011-T1A-2	13-1/1

\* When products will be discontinued, customers will be informed by HITACHI with twelve months prior announcement.

ACCEPTED BY;		PROPOSED BY; Da	n Ch	ma
KAOHSIUNG HITACHI	Sh.	7B64PS 2701- SP14Q011-T1A-2	PAGE	1 1/1
ELECTRONICS CO.,LTD.	No.	7B04F3 2701-3F14Q011-11A-2	PAGE	1-1/1

# RECORD OF REVISION

Sep.05,08   7864PS 2705 -   SP14Q011-T1A-2   Page 5-1/2   Page 5-1/2	DATE	SHEET No.			SUMMARY				
Page 5-1/2    Power Supply Voltage   VDD   3.0   5.0   5.25	Sep.05,'08	7B64PS 2705 –		HARA	CTERISTIC	CS			
Power Supply Voltage   VDD   3.0   5.0   5.25     Frame Frequency Note4   fFLM   70   75   -			Changed		0)//.55:			1	<del></del> 1
For Logic		Page 5-1/2		70					
Frame Frequency Note4			for Logic	)c	VDD	3.0	5.0	5.25	
ITEM SYMBOL MIN. TYP. MAX. Power Supply Voltage for Logic VDD 4.85 5.0 5.15 Frame Frequency Note4 fFLM 70 75 80			Frame Frequency N	ote4	fFLM	70	75	_	
Power Supply Voltage									_
Frame Frequency Note4   FLM   70   75   80				•	SYMBOL	MIN.	TYP.	MAX.	
AOHSILING HITACHI			Power Supply Voltage	ge	VDD	4.85	5.0	5.15	
AOHSILING HITACHI Sh			Frame Frequency N	ote4	fFLM	70	75	80	$\dashv$
AOHSILING HITACHI Sh				1					
AOHSILING HITACHI Sh		·	·						
AOHSIUNG HITACHI			·						
AOHSIUNG HITACHI									
AOHSIUNG HITACHI									
AOHSILING HITACHI Sh									
AOHSILING HITACHI Sh									
AOHSILING HITACHI Sh									
AOHSILING HITACHI Sh		·							
CAOHSILING HITACHI									
AOHSIUNG HITACHI									
AOHSIUNG HITACHI									
AOHSILING HITACHI Sh									
AOHSILING HITACHI Sh		·							`
CAOHSILING HITACHI Sh									
CAOHSILING HITACHI				•					
CAOHSILING HITACHI									
AOHSILING HITACHI Sh		·							
AOHSILING HITACHI Sh									
CAOHSILING HITACHI				÷					
AOHSILING HITACHI Sh									
CAOHSILING HITACHI				·			-		
CAOHSIUNG HITACHI Sh					•				
AOHSIUNG HITACHI Sh									
CAOHSIUNG HITACHI Sh									
AOHSIUNG HITACHI Sh						-			
CAOHSIUNG HITACHI Sh									
(AOHSIUNG HITACHI Sh.									
(AOHSIUNG HITACHI Sh.									
(AOHSIUNG HITACHI Sh. Sh.		·							
KAOHSIUNG HITACHI Sh.									
(AOHSIUNG HITACHI Sh.									
	AOHSILING	HITACHI	Sh						
ELECTRONICS CO.,LTD. DATE Sep.05,'08 No. 7B64PS 2702-SP14Q011-T1A-2 PAGE		IDA	.TELSen 05 '08 L = L	7B64P	S 2702-SP1	4Q011- <b>T</b>	Г1А-2  Р	AGE	2-1

# 3. GENERAL SPECIFICATIONS

(1) Part Name SP14Q011-T1A (2) Outer Dimensions 131.0(W)mm×102.2(H)mm×12.4(D)mm(typ.) (3) LCD Active Area 115.2(W)mm × 86.4(H)mm (4) Dot Size 0.345(W)mm × 0.345(H)mm (5) Dot Pitch 0.36(W)mm × 0.36(H)mm (6) Dot Number (Resolution) 320 (W)  $\times$  240 (H) dots 1/241 (7) Duty Ratio (8) LCD Type Transflective type F-STN Positive type (9) Viewing Direction 6 O'clock (10) Viewing Angle Wide Viewing Angle White LED (11) BackLight Type Life time: 40khrs @25°C Note: Life time for half of initial brightness (12) Touch Panel Resistance type The surface is antiglare type

### 4. ABSOLUTE MAXIMUM RATINGS

#### 4.1 ELECTRICAL ABSOLUTE MAXIMUM RATINGS

ITEM	SYMBOL	MIN.	MAX.	UNIT	COMMENT
Power Supply for Logic	VDD-VSS	-0.3	7.0	V	
Power Supply for LC Driving	Vcon-VSS	-0.3	3	V	
Input Signal Voltage	Vi	-0.3	VDD+0.3	V	Note 1
Input Signal Current	li	0	0.6	Α	
Static Electricity	VESD0	-	±100	V	Note 2,3,4
	VESD1	-	±10	kV	Note 2,3,5

VSS=0V: STANDARD

Note 1: DOFF, FLM, CL1, CL2, D0~D3.

Note 2: Make certain you are grounded when handling LCM.

Note 3 : Energy storage capacitance 200pF , discharge resistance 250  $\Omega$  Ta=25  $^{\circ}$ C , 60%RH.

Note 4: Contact discharge to I/F connector pins.

Note 5 : Contact discharge to front metal bezel.

#### 4.2 ENVIRONMENTAL ABSOLUTE MAXIMUM RATINGS

4.2 ENVITORMENTAL ABOOLOTE INDUMINOM TOTTINGO						
ITEM	OPERATING		STORAGE		COMMENT	
	MIN.	MAX.	MIN.	MAX.	COMMENT	
Ambient Temperature	<b>-20</b> ℃	<b>70</b> ℃	<b>-30</b> ℃	<b>80</b> ℃	Note 2,3	
Humidity	N <sub>1</sub>	ote 1	No	ote 1	Without Condensation	
Vibration		2.45m/s <sup>2</sup> (0.25G)	-	11.76m/s <sup>2</sup> (1.2G) Note 5	Note 4 1h max.	
Shock	_	29.4m/s <sup>2</sup> (3 G)	-	490.0m/s <sup>2</sup> (50 G) Note 5	X、Y、Z Directions	
Corrosive Gas	Not Acce	otable	Not Accep	table		

Note 1 Ta≦40°C : 85%RH max.

Note 2 Ta at  $-30 \, {\rm C} < 48 h$  , at  $80 \, {\rm C} < 168 h$ .

Note 3 Background color changes slightly depending on ambient temperature. This phenomenon is reversible.

Note 4 5Hz~100Hz (Except resonance frequency)

Note 5 This module should be operated normally after finish the test.

Note 6 The operating temperature only guarantee the display can be operated regarding the contrast, response time, brightness and other features related to the quality are judged by  $Ta = 25^{\circ}C$  condition.

KAOHSIUNG HITACHI	DATE	0 05 100	Sh.	700400 0704 0044 744 0	D40F	4.414
ELECTRONICS CO.,LTD.	DATE	Sep.05,'08	No.	7B64PS 2704- SP14Q011-T1A-2	PAGE	4-1/1

# 5. ELECTRICAL CHARACTERISTICS

# 5.1 ELECTRICAL CHARACTERISTICS

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT
Power Supply Voltage for Logic	VDD	-	4.85	5.0	5.15	<b>\</b>
Input Signal Voltage	Vi	H LEVEL	0.8VDD	-	VDD	V
Note 1	Vi	L LEVEL	0	-	0.2VDD	. V
Power Supply Current for Logic Note 2	IDD	VDD = 5.0V Vcon = 2.0V	-	(30)	-	mA
Power Supply Current for LC Driving Note 2	lcon	VDD = 5.0V Vcon= 2.0V	_	(0.4)	<b>-</b>	mA
Recommended LC Driving Voltage		VDD =5.0V Ta= 0℃ , <i>φ</i> =  0°	_	2.0	-	V
Note 2.3	Vcon	VDD =5.0V Ta=25℃, <i>∮</i> = 0°	1	2.0	-	V
		VDD =5.0V Ta=50°ℂ , <i>∮</i> = 0°	-	2.0	-	V
FRAME Frequency Note 4	fFLM	-	70	75	80	Hz

Note 1: DOFF, FLM, CL1, CL2, D0~D3

Note 2 : fFLM=(75)Hz, test pattern is all "Q".

Note 3 : Recommended LC driving voltage may fluctuate about  $\pm 1.0 V$  by each module. Test pattern is all "Q"

Note 4: Please set the frame frequency so as to avoid flicker and rippling on the display.


KAOHSIUNG HITACHI	DATE	0 05 200	Sh.	700400 0705 00440044 744 0		- A14	l
ELECTRONICS CO.,LTD.	DATE	Sep.05,'08	No.	7B64PS 2705- SP14Q011-T1A-2	PAGE	5-1/4	l


# 5.2 ELECTRICAL CHARACTERISTICS OF BACKLIGHT.

Ta=25°C (Backlight On)

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT
Power Supply Voltage for LED	VLED	-	-	5.0	_	٧
Power Supply Current for LED	ILED	VLED=5.0	-	160	200	mA

NOTE 1: The ILED changes depending on ambient temperature.





KAOHS	IUNG HITACHI	DATE	Sep.05,'08	Sh.	7B64PS 2705- SP14Q011-T1A-2	BACE	5 2 M	l
ELECTF	RONICS CO.,LTD.	DATE	Sep.05, 06	No.	/B04P3 2/05- SP 14Q011-11A-2	FAGE	5-2/4	ĺ

# 5.3 ELECTRICAL CHARACTERISTICS OF TOUCH PANEL

# 5.3.1 OPERATING CONDITION

ITEM	SPECIFICATION	NOTE
Operating Voltage	5VDC	7VDC max.
Operating Current	20mA max.	

#### 5.3.2 ELECTRICAL CHARACTERISTICS

ITEM		SPECIFICATION	NOTE
Resistance	XT-XB	210~880Ω	
Between Terminal	YR-YL	230~650Ω	
Insulation Resistance	X-Y	20M $\Omega$ min.	At 25V DC
Lincarity	Х	±1.5% max.	(Nieto 1)
Linearity	Υ	±1.5% max.	(Note 1)
Chattering	,	10ms max.	

#### 5.3.3 MECHANICAL CHARACTERISTICS

ITEM	SPECIFICATION	NOTE
Pen Input Pressure	0.2 ~ 1.2N	R0.8, Polyacetal Pen
Finger	0.2 ~ 1.2N	R8.0, Silicon Rubber
Surface Hardness	3H min.	JIS K 5400

#### 5.3.4 OPTICAL CHARASTERISTICS


ITEM	SPECIFICATION	NOTE
Transmittance	80% min.	

KAOHSIUNG HITACHI	D 4 TF	C 05 '00	Sh.	7DC4DC 2705	היכר	E 0/4
ELECTRONICS CO.,LTD.	DATE	Sep.05,'08	No.	7B64PS 2705- SP14Q011-T1A-2	PAGE	5-3/4

Note 1 : Operating Voltage 5V DC.

Note 2: Test Condition.

(a) X axis linearity testing method, 100g, VYR-VYL=5V, VOUT=VXT.




(b) Y axis linearity testing method, VXT-VXB=5V, VOUT=VYR.

#### Note 3: Calculation

(a) Y axis linearity

Linearity= 
$$\frac{\triangle E \text{ max.}}{EA - EH} \times 100(\%)$$



KAOHSIUNG HITACHI	DATE	Can 0E 100	Sh.	7D04D0 0705 0D440044 T44 0	DA 05	F 4/4
ELECTRONICS CO.,LTD.	DATE	Sep.05,'08	No.	7B64PS 2705-SP14Q011-T1A-2	PAGE	5-4/4

# 6. OPTICAL CHARACTERISTICS


6.1 OPTICAL CHARACTERISTICS OF LCD


Ta=25 °C (Backlight On)

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT	NOTE
Viewing Area	φF - φRR	K≧2.0	_	90	1	deg	1,2
Viewing Alea	φL - φRT	<b>N</b> ≦2.0		80		ueg	1,2
Contrast Ratio	К	φ=0°, θ=0°	3	5	-	_	3
Response Time (Rise)	tr	φ=0°, θ=0°	-	(150)	-	ms	4
Response Time (Fall)	tf	$\phi = 0^{\circ}$ , $\theta = 0^{\circ}$	••	(330)	-	ms	4

Note 1: Definition of Viewing Angle


(Measurement condition : HITACHI standard) Note 2~7 : See next page.






LEFT-RIGHT Direction


REAR-FRONT Direction





\* The viewing direction of this product is 6 O'clock. So  $f_F > f_{RR}$ 

Note 2 : Definition of viewing angle  $\phi_{RR}$  and  $\phi_F$  ,  $\phi_{RT}$  and  $\phi_L$ 




Contrast ratio K vs viewing angle  $\phi$ 


Viewing Angle

Note 3 : Definition of contrast "K"


K= Brightness on non-selected area (B2)

Brightness on selected area (B1)





Note 4: Definition of optical response time



Note 5 : HITACHI will not do 100% inspection for minimum value. Minimum value is for reference.

Note 6: HITACHI will do sampling inspection for minimum value.

Note 7: The LCD driving voltage should be adjusted at the voltage where the peak contrast is obtained.

KAOHSIUNG HITACHI		0 05 100	Sh.	7D04D0 0700 0D440044 T44 0	D 4 C E	
ELECTRONICS CO., LTD.	DATE	Sep.05,'08	No.	7B64PS 2706-SP14Q011-T1A-2	PAGE	6-2/3


#### 6.2 OPTICAL CHARACTERISTICS OF BACKLIGHT

ITEM	MIN.	TYP.	MAX.	UNIT	NOTE
Brightness	35	45	-	cd/m²	ILED=160mA Note 1
Brightness Uniformity	-	-	±30	%	-

Note 1 Display data should be all "ON".

The LCD driving voltage should be adjusted at the voltage where the peak contrast is obtained.

Note 2 Measure of the following 9 places on the display.




Definition of the brightness tolerance.

KAOHSIUNG HITACHI	DATE	Sep.05,'08	Sh.	7B64PS 2706- SP14Q011-T1A-2	DAGE	6 2/2
ELECTRONICS CO.,LTD.	DATE	Sep.05, 06	No.	7804F3 2706- 3F14Q011-11A-2	-AGE	0-3/3

# 7. BLOCK DIAGRAM Y320 <u>IC2</u> 320x240 dots Y160 **BACKLIGHT** T/P Y160 LED $\overline{c}$ <u>ဗ</u> Power Supply Circuit Timing Circuit VLED(-)-KAOHSIUNG HITACHI Sh. No. DATE Sep.05,'08 PAGE 7B64PS 2707-SP14Q011-T1A-2 7-1/1 ELECTRONICS CO., LTD.

# 8. INTERFACE TIMING CHART

# 8.1 INTERFACE TIMING CHART




KAOHSIUNG HITACHI	DATE	Sep.05,'08	Sh.	7B64PS 2708- SP14Q011-T1A-2	PAGE	8_1/3
ELECTRONICS CO.,LTD.	DAIL	Зер.00, 00	No.	7 DO41 3 2700- 3F 14Q011-11A-2	I AGE	0-1/3

# 8.2 TIMING CHARACTERISTICS

VDD=5.0±5%


PARAMETER	SYMBOL	MIN.	TYP.	MAX.	UNIT	CONDITION
Shift Clock Period	twck	71	-	-	ns	tr , tf≦10ns
Shift Clock "H" Pulss Width	tWCKH	23	-	_	ns	
Shift Clock "L" Pulss Width	tWCKL	23	-	-	ns	
Data Setup Time	tDS	10	-	-	ns	
Data Hole Time	tDH	20		-	. ns	
Latch Pulse "H" Pulse Width	tWLPH	23	-	-	ns	
Shift Clock Rise to Latch Pulse Rise Time	tLD	0	-	-	ns	
Shift Clock Rise to Latch Pulse Fall Time	tsL	25	-	· <u>-</u>	ns	
Latch Pulse Rise to Shift Clock Rise Time	tLS	25	<u>.</u>	-	ns	
Latch Pulse Fall to Shift Clock Fall Time	tLH	25	-	1	ns	
Input Signal Rise Time	tr	-	-	50	ns	(Note 1)
Input Signal Fall Time	tf	-	1	50	ns	(Note 1)
DOFF Removal Time	tsD	100	-	_	ns	
DOFF Enable Pulse Time	tWDL	1.2			$\mu$ s	
"FLM" Set Up Time	tFS	30	-		ns	-
"FLM" Hold Time	<b>t</b> FH	50	-	-	ns	*

Note 1: (twck-twckh-twckl)/2 is the maximum in the case of high speed operation.



KAOHSIUNG HITACHI		C 05 '00	Sh.	7D04D0 0700 0D440044 T44 0	DAGE	0.070
ELECTRONICS CO.,LTD.	DATE	Sep.05,'08	No.	7B64PS 2708- SP14Q011-T1A-2	PAGE	8-2/3

# 8.3 TIMING OF POWER SUPPLY AND INTERFACE SIGNAL



Note 1 : DOFF function takes priority even if the input signal status becomes irregular immediately after VDD power-on.

Note 2 : Please keep the specified sequence because wrong sequence may cause permanent damage to the LCM.

# 9. DIMENSIONAL OUTLINE 131.0±0.5(LCM Outline) 129.0±0.5(T/P Outline) (0.6)5.9 max.(T/P Cushion Area) 1.7 max.(T/P Cushion Area) 119.4±0.3(Window of Bezel)/( T/P Viewing Area) 3.3±0.3 117.2±0.3( LCD Viewing Area) 4.5±0.4 3.5±0.3 (0.6) 1.9 max.(T/P Cushion A 116.6±0.3(T/P Active Area) 4.8±0.4 115.2±0.1 (LCD Active Area) 5.5±0.3 12.4±0.5 4.8±0.4 4.5±0.4 (63.1)10.9±0.5 4.(Ø2.5) 90.6±0.3 (Window of Bezel)/( T/P Viewing Area) (51.1) 86.4±0.1 ( LCD Active Area) Outline) (79.08)Active Area Center Pin1 102.2±0.5(LCM CN2 (80.0)CN1 Viewing Direction Insert Direction (13.2) 5.7 max.(T/P Cushion Area) (70.8)3.0±0.5 125.0±0.5 Scale: NTS Unit : mm KAOHSIUNG HITACHI 7B63PS 2709-SP14Q011-T1A-2 | PAGE | 9-1/2 DATE | Sep.05,'08 ELECTRONICS CO.,LTD.

# 

#### 9.3 INTERFACE PIN CONNECTION

CN1 Molex: 52893-2095(Suitable FPC: t0.3±0.05mm,0.5±0.05mm pitch)

0.36

-			·······		mm,0.5±0.05mm pitch)
	FACE	PIN No.	SIGNAL	LEVEL	FUNCTION
LCM	CN1	1	N.C	-	No Connection
		2	N.C		No Connection
		3	VSS	-	GND
		4	D0		
		5	D1	   H/L	Display Data
		6	D2	11/2	Display Data
		7	D3		
		8	VSS	-	GND
		9	. CL2	H→L	Display Data Shift
		10	VSS	<u>-</u>	GND
		11	Vcon	-	Contrast Adjust
		12	VDD	-	Power Supply for Logic
		13	FLM	Н	First Line Marker
		14	DOFF	H/L	H:ON / L:OFF
		15	CL1	H→L	Display Data Latch
		16	VSS	-	GND
		17	XT	-	Analog Signal Form Digitizer Top
		18	YL	-	Analog Signal Form Digitizer Left
		19	XB	-	Analog Signal Form Digitizer Bottom
		20	YR	_	Analog Signal Form Digitizer Right

Unit: mm

Measurement tolerance: ±0.1

CN2 JST Housing: BHR-03VS-1

PIN No.	SIGNAL	LEVEL	FUNCTION
1	VLED(+)	-	Power Supply for LED
2	NC	-	No connection
3	VLED(-)	_	GND for LED


KAOHSIUNG HITACHI		Sep.05,'08	Sh.	7DC4DC 2700 CD44C044 T4A 2	DACE	0.2/2
ELECTRONICS CO.,LTD.	DATE	, , ,	No.	7B64PS 2709- SP14Q011-T1A-2	PAGE	9-212

# 10. APPEARANCE STANDARD


#### 10.1 APPEARANCE INSPECTION CONDITION

Visual inspection should be done under the following condition.

- (1) The inspection should be done under in the dark room. (about 1000(lx),500(lx)min. and non-directive)
- (2) The distance between eyes of an inspector and the LCD module is 25cm.
- (3) The viewing zone is shown the figure . Viewing angle  $\leq 25^{\circ}$



#### 10.2 DEFINITION OF EACH ZONE



KAOHSIUNG HITACHI	~~ <u>-</u>	Sep.05,'08 Sh.	7B64PS 2710- SP14Q011-T1A-2	PAGE	10 1/4
ELECTRONICS CO.,LTD.	JATE	No.	7B04F3 27 10- 3F 14Q0 11-1 1A-2	FAGE	10-1/4

# 10.3 APPEARANCE SPECIFICATION

\*) If a problem occurs in respect to any of these items, both parties(Customer and HITACHI) will discuss in more detail.


No.	ITEM	CRITERIA						
	Scratches	, •	Distinguished one is not acceptable (To be judged by HITACHI limit sample)					
	Dent	Same as above						
	Wrinkles in Polarizer	Same as above				*	_	
	Bubbles	Average di	ameter	Ma	ximum number			
		D(mm	า)		acceptable			
		D≦	0.2		Ignore			
		0.2 <d≦< td=""><td><b>≦</b>0.3</td><td></td><td>12</td><td></td><td>  -  </td></d≦<>	<b>≦</b> 0.3		12		-	
		0.3 <d≦< td=""><td>≦0.5</td><td></td><td>3</td><td></td><td></td></d≦<>	≦0.5		3			
		0.5 <d< td=""><td></td><td></td><td>None</td><td></td><td></td></d<>			None			
	Stains,		Filame	ntous				
	Foreign Materials,	Length	Width		Maximum number		-	
	Dark Spot	L(mm)	W(mn		acceptable			
		L≦2.0	W≦0		Ignore			
١,		L≦3.0	0.03 <w≦< td=""><td></td><td>6</td><td></td><td></td></w≦<>		6			
L		L≦2.5	<u>  0.05<w≦< u=""></w≦<></u>		1	<u> </u>		
		,	Rou			_		
		Average diameter	Maximum r		Minimum			
c		D(mm)	accepta		space			
-	,	D<0.2	Ignor	е	<u>-</u>	$\bot$	-	
	•	0.2 ≦D<0.33	8		10mm	_		
		0.33≦D	None		-	_		
D		Total	Filamentous					
		Those wiped out		•				
	Color Tone	To be judged by	/ HITACHI lir	nit samp	ele	10	-	
	Color Uniformity	Same as Above				$\frac{10}{10}$	-	
	Pinhole	Average di			kimum number			
		D(mm D≦0.	<del></del>		acceptable			
					Ignore			
	·	0.15 <d≦0.3 C≦0.0</d≦0.3 			10			
	Contrast	Average Average	Contrast	Maxim	ignore um Minimum	$\frac{1}{2}$		
	Irregularity	diameter	Contrast	numb			-	
	(Spot)	D(mm)		accepta			.	
	(0,000)	D≦0.25	To be	Ignor				
		0.25 <d≦0.35< td=""><td>judged by</td><td>10</td><td>20mm</td><td></td><td></td></d≦0.35<>	judged by	10	20mm			
		0.25 < D ≦ 0.55 0.35 < D ≦ 0.5	HITACHI	4	20mm	-		
		0.5 < D	, (01)	None				
	L	, -, -, -, -, -, -, -, -, -, -, -, -, -,		11011	~l		L	

KAOHSIUNG HITACHI	D 4 TF	0 05 100	Sh.	770470 0740 07440044 744 0	DAGE	40.04
ELECTRONICS CO.,LTD.	DATE	Sep.05,'08	No.	7B64PS 2710- SP14Q011-T1A-2	PAGE	10-2/4

No.	ITEM		CRITERIA				
	Contrast Irregularity (Line)	Width D(mm)	Length L(mm)	Maximum number acceptable	Minimum space		
L	(Filamentous)	W≦0.25	L≦1.2	2	20mm		
С		W≦0.2	L≦1.5	3	20mm		-
D		W≦0.15	L≦2.0	3	20mm		
		W≦0.1	L≦3.0	4	20mm		
		То	tal	6			
	Rubbing Scratch	To be judged	To be judged by HITACHI standard				-


Note

(1) Definition of average diameter D




$$D = \frac{a+b}{2}$$

(2) Definition of length L and width W



(3) Definition of pinhole



c : Salience

# (3)Touch panel appearance

Visual inspection should be done under the following condition.

- \*) The inspection should be done in a dark room. (about 1000(lx),500(lx)min. and non-directive)
- \*) The distance between eyes of an inspector and the LCD module is 30 cm.

No.	ITEM	CRITERIA				APPLIED ZONE	
	Scratches	Width W(mm)		ngth nm)	Maximum number acceptable		
		W>0.1	L≧	:10	None	А,В	
		0.10≧W>0.05	L<	(10	4 pcs max.		
		0.05≧W	L<	10	Ignored		
	Foreign	Fil	amentous	(Line sha	pe)		
T 0	Materials	Width W(mm)	l	ngth nm)	Maximum number acceptable		
U		W>0.10	-		Dust (circular)	A,B	
CH		0.10≧W>0.05	3 <l< td=""><td>None</td><td></td></l<>		None		
"		0.05≧W	L≦	<u>≤</u> 3	Ignored		
P		Round(Dot shape)					
A N		Average diam D(mm)	eter		imum number acceptable	A,B	
E		D>0.35		None			
L		0.35≧D>0.2	25	6 psc max.		В	
		D≦0.25		Ignored		A,B	
	Newton Ring (Touch Panel)	Need to discuss with customer				A,B	
	Touch Panel Uncleanliness	No conspicuous dirt				А	
	Rubbing Scratch	To be judged by HIT	ACHI stan	dard			

# (4) Glass indentation

ITEM	SPECIFIC	CATIONS
Common Indentation	X	X         Y         Z           ≤5.0         ≤3.0         ≤T
Corner Broken	Z	X   Y   Z   ≤3.0   ≤3.0   ≤T
Proceeding Crack		None

KAOHSIUNG HITA	ACHI DATE	Sep.05,'08	Sh.	7B64PS 2710- SP14Q011-T1A-2	DVCE	10 4/4	
ELECTRONICS C	O.,LTD.	Sep.05, 06	No.	7B04P3 27 10- SP 14Q011-11A-2	FAGE	10-4/4	

#### 11 PRECAUTION IN DESIGN

11.1 LC DRIVING VOLTAGE (VLCD) AND VIEWING ANGLE RANGE
Setting VLCD out of the recommended condition will be a cause for a change of viewing angle range.

#### 111.2 PRECAUTIONS AGAINST STATIC CHARGE

As this module contains C-MOS LSIs, it is not strong against electrostatic discharge. Make certain that the operator's body is connected to the ground through a list band etc. And don't touch I/F pins directly.

#### 11.3 POWER ON SEQUENCE

Input signals should not be applied to LCD module before power supply voltage is applied and reaches to specified voltage (VDD).

If above sequence is not kept, C-MOS LSIs of LCD modules may be damaged due to latch up problem.

#### 11.4 PACKAGING

- (1) No leaving product is preferable in the place of high humidity for a long period of time. For their storage in the place where temperature is 35 ℃ or higher, special care to prevent them from high humidity is required. A combination of high temperature and high humidity may cause them polarization degradation as well as bubble generation and polarizer peel-off. Please keep the temperature and humidity within the specified range for use and storage.
- (2) Since polarizers tend to be easily damaged, They should be handled full with care so as not to get them touched, pushed or rubbed.
- (3) As the adhesives used for adhering polarizers are made of organic substances which will be deteriorated by a chemical reaction with such chemicals as acetone, toluene, ethanol and isopropyl alcohol. The following solvents are recommended for use: Normal hexane Please contact us when it is necessary for you to use chemicals.
- (4) Lightly wipe to clean the dirty surface with absorbent cotton waste or other soft material like chamois, soaked in the chemicals recommended without scrubbing it hardly. To prevent the display surface from damage and keep the appearance in good state, it is sufficient, in general, to wipe it with absorbent cotton.

- (5) Immediately wipe off saliva or water drop attached on the display area because its long period adherence may cause deformation or faded color on the spot.
- (6) Foggy dew deposited on the surface due to coldness will be caused for polarizer damage, stain and dirt on product. When necessary to take out the products from some place at low temperature for test, etc. It is required for them to be warmed up in a container once at the temperature higher than that of room.
- (7) Touching the display area and contact terminals with bare hands and contaminating them are prohibited, because the stain on the display area and poor insulation between terminals are often caused by being touched by bare hands. (Some cosmetics are detrimental to polarizers.)
- (8) In general the quality of glass is fragile so that it tends to be cracked or chipped in handling, specially on its periphery. Be careful not to give it sharp shock caused by dropping down, etc.

#### 11.5 CAUTION FOR OPAERATION

- (1) It is an indispensable condition to drive LCDs within the specified voltage limit since the higher voltage than the limit causes the shorter LCD life. An electrochemical reaction due to direct current causes LCDs undesirable deterioration, so that the use of direct current driver should be avoided.
- (2) Response time will be extremely delayed at lower temperature than the operating temperature range and on the other hand at higher temperature LCDs show dark blue color in them. However those phenomena do not mean malfunction or out of order with LCDs which will come back in the specified operating temperature range.
- (3) If the display area is pushed hard during operation, some font will be abnormally displayed but it resumes normal condition after turning off once.
- (4) A slight dew depositing on terminals is a cause for electrochemical reaction resulting in terminal open circuit. Usage under the relative condition of 40 ℃ 50%RH or less is required.

#### 11.6 STORAGE

- In case of storing for a long period of time (for instance, for years) for the purpose of replacement use, the following ways area recommended.
- (1) Storage in a polyethylene bag with the opening sealed, so the fresh air will not be entered from outside.
- (2) Placing in a dark place where neither exposure to direct sunlight nor light is, keeping temperature in the range from  $0^{\circ}$ C to  $35^{\circ}$ C.
- (3) Storing with no touch on polarizer surface by anything else. (It is recommended to store them as they have been contained in the inner container at the time of delivery from us.)


#### 11.7 SAFETY

- (1) It is recommendable to crash damaged or unnecessary LCDs into pieces and wash off liquid crystal by either of solvents such as acetone and ethanol, which should be burned up later.
- (2) When any liquid leaked out of a damaged glass cell comes in contact with your hands, please wash it off well with soap and water.

# 12. DESIGNATION OF LOT MARK

LOT MARK

Lot mark is consisted of 4 digital number.



YEAR	FIGURE IN
·	LOT MARK
2008	8
2009	9
2010	0
2011	1
2012	2

Note 1. Some products have alphabet at the end or the first.

	FIGURE IN		FIGURE IN
MONTH	LOT MARK	MONTH	LOT MARK
Jan.	01	Jul.	07
Feb.	02	Aug.	08
Mar.	03	Sep.	09
Apr.	04	Oct.	10
May	05	Nov.	11
Jun.	06	Dec.	12

WEEK	FIGURE IN
(DAY IN	LOT MARK
CALENDAR)	
01~07	1
08~14	2
15~21	3
22~28	4
29~31	5

Location of lot mark: on the back side of LCM

8111T

#### 13. PRECAUTION FOR USE

- 13.1 A limit sample should be provided by the both parties on an occasion when the both parties agreed its necessity. Judgment by a limit sample shall take effect after the limit sample has been established and confirmed by the both parties.
- 13.2 On the following occasions, the handling of the problem should be decided through discussion and agreement between responsible persons of the both parties.
  - (1) When a question is arisen in the specifications.
  - (2) When a new problem is arisen which is not specified in this specifications.
  - (3) When an inspection specifications change or operating condition change in customer is reported to HITACHI, and some problem is arisen in this specification due to the change.
  - (4) When a new problem is arisen at the customer's operating set for sample evaluation in the customer site.

The precaution that should be observed when handling LCM have been explained above. If any points are unclear or if you have any request, please contact HITACHI.